GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

Industries & Commerce Department – YSR Steel Corporation Limited - Construction of Intake arrangements at Mylavaram Reservoir and laying of 1500 mm dia MS pipeline for drawing 2 TMC of water to the proposed integrated steel Plant at Sunnapurallapalli and peddandluru villages of Jammalamadugu Mandal, YSR Kadapa district with an out lay of Rs.126.29 Crs. – Administrative Sanction – Orders – Issued.

INDUSTRIES & COMMERCE (P&I) DEPARTMENT

G.O.Ms.No.31 Dt: 06.05.2023

Read the following:

1. G.O.Ms.No.105, III & Com. (P&I) Dept., Dated 4-12-2019
2. G.O.Ms.No.106, III & Com. (P&I) Dept., Dated 4-12-2019
3. G.O.Ms.No.72, Ind. & Com. (P&I) Dept., dated 28-10-2020
4. G.O.Rt. No.52, Revenue (Lands.VI) Dept., Dated 03-03-2021.
5. GO Ms No.84, Water Resources (Reforms) Dept. dt. 20.12.2019.
6. GO Ms No.13, Water Resources (Reforms) Dept. dt. 15.03.2021.
7. G.O.Ms.No.87, Industries and Commerce (P&I) Department, dated 21.12.2022
8. e-file from MD, YSRSCL No. APIIC-16024/37/2021-CE I-ENGG WNG-APIIC (Computer No.1461152)

ORDER:

In the reference 1st read above, Government have accorded approval for setting up of an Integrated Steel Plant at Sunnapurallapalli and Peddandluru villages of Jammalamadugu (M) in YSR Kadapa Dist.

2. In the reference 2nd & 3rd read above, a new company "AP High Grade Steels Limited" was incorporated by the Nodel officer and Government has ratified the action of incorporation and orders have been issued for the change of name from "AP High Grade Steels Limited" to "YSR Steel Corporation Limited".

3. In the reference 4th read above, Government allotted land to an extent of Ac 3,148.68 cents to YSRSCL at Sunnapurallapalli and Peddandluru villages of Jammalamadugu (M) of YSR Kadapa district.

4. In the reference 5th read above, Government accorded permission for allocation of 2.00 TMC of water for industrial use from the Gandikota Reservoir to the Integrated Steel Plant at Sunnampurallapalli and Peddandluru Villages of Jammalamadugu Mandal, YSR Kadapa District subject to payment of water royalty charges @ Rs. 5.50/- per 1000 gallons and at the rates fixed by the Government from time to time.

5. In the reference 6th read above, Government accorded permission for change of only water tapping location from Gandikota Reservoir to Mylavaram Reservoir, for drawl of 2 TMC of water to the proposed site of M/s A.P. High Grade Steels Ltd., YSR Kadapa District.

6. In the reference 7th read above, Govt. have issued orders approving the proposal of JSW Steel Limited for establishment of 2 MTPA Steel Plant in two phases with an investment of Rs.8,800 Crores at Sunnapurallapalli Village of Jammalamadugu Mandal, YSR Kadapa District subject to the following conditions fulfilled by the YSRCL as specified at para 6-(a)(iii), (iv) and (v) in the aforesaid Government Orders. As per para-6 (a)(v)(b) of the said GO., YSRSCL has to provide 15 kilometres long pipeline (including acquisition of the right of way for

such pipeline) along with the necessary pumping infrastructure from Gandikota reservoir for an assured water supply of 2 TMC per annum.

7. In the reference 8th read above, the MD, YSRSCL has stated that the TCE, the consultant for the preparation of DPR in respect of above proposal has prepared the estimate for the construction of intake well at Mylavaram and the pumping arrangements including the pipeline (1500 mm dia MS) for drawing the water from Mylavaram as per the SoR, 2021-22 for Rs. 130.75 Crs. Meanwhile, the cost of the materials and steel have been increased due to the change in SoR and the component of GST also been raised from 12% to 18%. Therefore, the estimate has been re-casted as per the present SoR 2022-23 which worked out to Rs. 145 Crs.

8. The MD, YSRSCL has therefore requested the Govt. to accord administrative sanction for the work "Construction of Intake arrangements at Mylavaram Reservoir and laying of 1500 mm dia MS pipeline for drawing 2 TMC of water to the proposed integrated steel Plant at Sunnapurallapalli and peddandluru villages of Jammalamadugu mandal, YSR Kadapa district with an out lay of Rs. 131.30 Crores as follows:-

Name of Work: Construction of Intake Arrangements at Mylavaram Reservoir and Laying MS pipeline of 1500mm dia. (12.5 Kms) for drawing 2 TMC of water to the proposed Integrated Steel Plant at Sunnapurallapalli and Peddanandluru villages of Jammalamadugu Mandal, YSR Kadapa Dist.

Sl No	Description	Components	Estimate	Remark
A	Construction works			
1	Intake will construction	1. Coffer dam inside the reservoir using impervious material & Dewatering. 2. Intake well of 15 m Dia 3. Approach bridge by open foundation - 200 Rmt 4. Installing of Vertical pumps - 2 Nos (1W+1S) - 50% standby 5. Erecting of Gantry girder for accommodating lifting of pumps during maintenance 6. Providing NRV, dismantling joint and Butterfly valves. 7. Electrical Setup.	20.61	
2	Pipeline	1. Pipe Line of 1500mm dia with internal Epoxy coating & External Guniting MS pipe line - Length -12.5 Kms 2. Valves + Valve Chambers (50 nos) 3. Thrust Block (22 nos) 4. Anchor Blocks (6 nos) 5. Crossings (5 nos) 6. Air vessels (105 m3 2 nos) 7. Termination Room (5mx5m)	79.53	
Sub Total - Works			100.13	
B	Taxes & others			
1	Provision for Quality control @ 0.75%		0.75	
2	Price Adjustment @ 5%		5.01	
3	Provision towards Payable to other dept/Design vetting - 1 %		1.00	
4	Provision for seigniorage Charges		1.58	
5	Provision for NAC @ 0.1%		0.10	

6	Provision for GST (Part A) @ 18 %	18.02	
7	Provision towards PMC Charges - 2 %	2.00	
8	Provision for Unforeseen items @1.5 %	1.50	
9	PS & Contingencies @ 1 %	1.00	
10	Rounding off	0.20	
	Sub Total - Taxes & Others	31.17	
	Grand Total (Part A+ Part B)	131.30	

9. Government after careful examination of the matter hereby accord administrative sanction for the work "Construction of Intake arrangements at Mylavaram Reservoir and laying of 1500 mm dia MS pipeline for drawing 2 TMC of water to the proposed integrated steel Plant at Sunnapurallapalli and peddandluru villages of Jammalamadugu Mandal, YSR Kadapa district with an out lay of Rs.126.29 Crs". The component of price adjustment @ 5% proposed in the estimate will be considered at Revised Estimate level as per actual in terms of the G.O.Ms.No.62, Water Resources Dept., Dt:30-11-2021.

10. The expenditure sanctioned in para-9 above shall be met from the HoA:4875-60-800-11-SH(09)-530/531 from out of the budget made available for the financial year 2023-24.

11. The Managing Director, Y.S.R. Steel Corporation Limited shall take further necessary action accordingly.

12. This order is issued with the concurrence of Finance Department vide their U.O.No.FIN01-FMU0MRAS(IC)/1/2021-FMU-IIEIC Dt:02.05.2023. (Computer No.1475628).

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

R KARIKAL VALAVEN
SPECIAL CHIEF SECRETARY TO GOVERNMENT & CIP

To
The Managing Director, Y.S.R. Steel Corporation Limited, 10th Floor, APIIC Towers, Mangalagiri.
Copy to:
The PS to Minister for Industries
The P.S. to Spl. Chief Secretary to Government & CIP, I&C Department.
The P.S. to Secretary to Government (Mines & Geology), I&C Department.
The Water Resources (Reforms) Department.
The Finance (FMU-I&I, Energy and I&C) Department.
The District Collector, Y.S.R. Kadapa District.
SF/SC.

//FORWARDED:: BY ORDER//

S. Sasikalatha
SECTION OFFICER